

QUOTATION

M-45-44, Zainab Towers Link Road Model Town Lahore. 042-3594626-145

Customer: Name: Mr.Akhtar

> Faisalabad City

Phone:

40.25KW ON-Grid Comments or Special Instructions:

Solar System With IP65 Inverter

SALES MANAGER	QT. NUMBER	DATE	VALID TILL	SOLAR PV	TERMS
Nadeem Baig	SOLDT-OS024510	28/03/2024	2 Days	40,250	80% Advance

ITEM	DESCRIPTION	QTY	Unit Rate	AMOUNT
SOLAR PANEL	575 Watts Mono Perc Half Cut Cell Longi Solar HiMO6 Tier1	70	29,900	PKR 2,093,000.00
INVERTER	40KW IP65 ON-Grid Solar Inverter 1000Voc DC 6 MPPT SCC	1	755,000	PKR 755,000.00
BATTERY BANK	48V/100AH Lithium-lon Battery Narada/Huawei/Vision	1	350,000	PKR 0.00
PV FRAMES	Roof Mounting Stand Galvanised 14Guage L2/L3	70	3,700	PKR 259,000.00
PV COMBINING WIRES	Cables to combine solar panels 6/10mm Inverter Tin Cotted	10	22,500	PKR 225,000.00
INSTALLATION	Installation & Labour	40,250	4	PKR 161,000.00
DISTRIBUTION	Duct Piping Clamps Joints, Delivery	1	35,000	PKR 35,000.00
NET METERING	Net Metering Complete Process without Load Section	1	350,000	PKR 350,000.00
D. B BOX	D. B Braker AC/DC Change Over, Internal electric work etc	1	75,000	PKR 75,000.00
EARTHING	Earthing Boring 50Feet Deep with Cut off Switch, Arrester	1	85,000	PKR 85,000.00
Warranty:			Total	PKR 4,038,000.00
Solar Panel	12 Years 25 Years Life			
Inverter	5 Year Warranty			
Battery/Cell	3 Year Warranty		Final Total	PKR 40,38,000.00

TERMS & CONDITIONS

- 80% Payment in Advance, 20% Before installation Complete.
 Any Type of Civil work not included. Internal Electric Cable Not included in this price.
- 3. Goods delivery Will be after 80% confirmation of the payment.
- Confirmation Order: By Proceeding of Payment to Solar Dynamics Technologies Pakistan
 Damages, Burnout and Broken Devices, Equipment, System or Product is not covered in Warranty.
- Project Execution: Once Goods are delivered to customer destination.
 Delivery Charges not Included in this Quotation, Will be as per Actual

To acce	pt this (quotation.	sign	here	and return:	

THANK YOU FOR YOUR BUSINESS!